

LuminaVesta





Critical Measurements and Installation Guidelines Upright Support System

Anchoring:	Uprights are anchored to the wall, requiring 1/2" plywood backing, secured to the studs and resting on the floor to offload vertical stress from the studs.
Wall Preparation:	Plywood backing should be installed prior to sheetrock, ensuring uprights can be securely attached through both sheetrock and plywood.
Fasteners:	Use screws that are at least 1/4" longer than the combined thickness of the plywood and sheetrock to ensure a secure fit.
Back Panels Connection:	Attached to the uprights via mechanical clips for easy assembly and disassembly, providing flexibility in design and use.

Accessories Installation

Components:	Shelves, hanging rods, and base drawers are affixed to the uprights using metal brackets for a sturdy and reliable setup.
Alignment:	Installation must be perfectly level for optimal functionality. Uprights should be aligned consistently based on hole perforations to accommodate brackets correctly. Installation Tips
Blocking Requirement:	Ensure the wall has the necessary blocking in place before installation. The blocking supports the uprights and distributes the load evenly across the wall.
Leveling:	Use a high-quality level during installation to ensure all components are perfectly horizontal or vertical, as required.
Directionality:	Pay attention to the orientation of the uprights. They must be installed in the correct direction (up or down) to match the perforations with the brackets.

For additional assistance or inquiries about the LuminaVesta guarderobe system, please contact our support team at www.ldlicf.com